EMS MEMORIAL CO-OPERATIVE HOSPITAL
& RESEARCH CENTRE, PERINTHALMANNA
NABH Accredited and ISO 9001-2015 Certified Multi Super Speciality Hospital
P.B. No. 25, PERINTALMANNA - 679 322.
PHONE: 04933 225751-225755, 276 000, 353 000
email : info@emshospital.org.in, emshospital@rediffmail.com website : www.emshospital.org.in

EMCH/CON/ADV/29/2026 19/11/2026

NOTICE INVITING QUOTATIONS

Sealed quotations are invited from experienced contractors or authorized agencies for the complete removal of the existing vinyl flooring and providing & laying new vinyl flooring in the CT Scan Gantry Room at the Main Block Building, by the General Manager EMS Co-operative Hospital, Perinthalmanna, strictly adhering to the technical specifications given below.

1. Work Description & Technical Specifications:

- Name of Work: Replacement of existing vinyl flooring with new vinyl flooring in the CT Scan Gantry Room (Main Block Building).
- Approximate Area: 37 Sq.m - Exact measurements must be verified at the site prior to execution.

2. Material Specifications:

- Providing and laying 2mm thick homogeneous Vinyl flooring in roll form of width not less than 1.2m (of approved equivalent).
- All joints, including coving rounded junctions between the floor and wall, must be joined by cord welding to make the surface completely seamless at all levels as per manufacturer specifications.
- The wear surface must consist of an impregnated polyurethane homogeneous mixture of PVC, plasticizers, urethane, color pigments, and filler calendared to form a sheet without backing. Colors and pattern details must be dispersed throughout the thickness of the wear layer.
- Quality Standards: The sheet must conform to the requirements of BS EN 649:1997 ("Standard Specification for Vinyl Sheet Floor Covering without backing"), Group P Wear Resistance as per EN 660-2, Fire Resistance (Critical Radiant Flux) of more than 11 kW/m^2 as per ISO 9329-1, and Slip Resistance of R9 as per Oil Wet Ramp test (AS 4586).

3. **Terms & Conditions:**

1) The quoted rate shall be all-inclusive, covering the cost of materials, removal of existing flooring, surface preparation, application, work at all levels, delivery, loading/unloading charges, and applicable taxes (GST).

2) All guarantees/warranties provided by the manufacturer must be officially passed on to the hospital management upon completion and handover of the work.

3) Preference will be given to contractors/firms with proven experience in executing similar vinyl flooring works in hospitals or healthcare facilities. Details of previous works completed should be enclosed with the quotation.

4) Bidders are advised to inspect the site personally to verify exact dimensions and site conditions before submitting their quotations.

5) The work must be executed and completed within the stipulated timeframe from the issuance of the Purchase & Work Order, ensuring minimal disruption to the functioning of the CT Scan department.

6) The Hospital Management reserves the right to accept or reject any or all quotations without assigning any reason whatsoever.

Interested contractors/agencies may submit their sealed quotations superscribed "Quotation for Vinyl Flooring Works in CT Scan Gantry Room" on the envelope, so as to reach the undersigned on or before 26/11/2026 at 11:00 AM.

Perinthalmanna

General Manager

Notice to be published.

1. Hospital Website
2. Hospital Notice Board
3. Thazhekkode Grama panchayath office
4. Thazhekkode village office
5. Perinthalmanna municipal office
6. Perinthalamanna taluk office
7. Perinthalmanna Block Development office
8. Co-operative Assistant Registrar Office